BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38905

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/18/2019-20, Date: 16.11.2019

Improvements of Roads, drains and culverts at Lottegollahalli Devinagar and surrounding area at Kodigehalli ward no 08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GANGULU REDDY A ( )		
				In Figures		In Words
1	518.4	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	300.0	155520.00	Rupees Three Hundred Only
2	64.8	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (Page No. 13 / Item No. 4.2 PWD SR 2018-19	Cum	5500.0	356400.00	Rupees Five Thousand Five Hundred Only
3	12.96	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.6 PWD SR 2018-19	Cum	5800.0	75168.00	Rupees Five Thousand Eight Hundred Only
4	155.52	Providing laying palin / reinforced cement concrete for side drains using M 20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed well compacted for walls and bottom including cenmtering shuttering form work etc. complete as per approved drawing and design MORTH Specification No. 1500,1700,2200 Wall & Bottom thickness 15cm Page No. 271, Item No. 37.59.2, PWD SR 2018-19	Cum	7100.0	1104192.00	Rupees Seven Thousand One Hundred Only
5	9.33	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 Page No. 18 / Item No. 4.46.2, PWD SR 2018-19	Tonne	75200.0	701616.00	Rupees Seventy Five Thousand Two Hundred Only
6	388.8	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - Data rate	Sqm	2300.0	894240.00	Rupees Two Thousand Three Hundred Only
7	960	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 27 / Item No. 5.30 PWD SR 2018-19	No	432.0	414720.00	Rupees Four Hundred Thirty Two Only
8	194.4	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 / Item No. Item No. 15.80, PWD SR 2018-19	Sqm	40.0	7776.00	Rupees Forty Only

A. Gangulu Reddy

Signature of the contractor

30/04

Executive Engineer

30/04

	Approved Qty	Description	Unit	Approved Tender Rates of GANGULU REDDY A ( )		
				In Figures		In Words
9	194.4	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19	Sqm	95.0	18468.00	Rupees Ninety Five Only
10	715.5	Removing and refixing stone slabs of drains and pointing in CM (1:3) Page No. 27 / Item No. 5.33 PWD SR 2018-19	Sqm	200.0	143100.00	Rupees Two Hundred Only
11	71.55	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete Page No. 27 / Item No. 5.31.1 PWD SR 2018-19	Sqm	780.0	55809.00	Rupees Seven Hundred Eighty Only
12	422.4	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 27 / Item No. 5.26.2, PWD SR 2018-19	Sqm	1181.0	498854.40	Rupees One Thousand One Hundred Eighty One Only
13	471.6	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - (Data rate Approved).	Sqm	2500.0	1179000.00	Rupees Two Thousand Five Hundred Only

A. Gangulu Reddy

Signature of the Contractor

30/04

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/04